

Price quote for:	1.0 PRICE SCHEDULE DUMP BOX	
Vendor Name:	Iron Valley Equipment & Mfg. - St Cloud	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	601 Franklin Ave NE	
P.O. Box:		
City, State, Zip:	St Cloud, MN 56304	
Phone #:	320-281-3335 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Vendor Name:	Iron Valley Equipment & Mfg. - West Fargo	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	860 9th St NE Suite I	
P.O. Box:		
City, State, Zip:	West Fargo, ND 58078	
Phone #:	701-353-5226 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Item #	Information Requested	Answer
1.0	Box Make and Model	Iron Valley Contractor
	List Truck Type Box Fits	Single Axle/Tandem Axle
	Box Style	Contractor
	Width & Length of Box	100"
	Side Panel Description	10 gauge, 14" Split Fold Sides
	Front Panel Description	10 gauge, 42" - 62" Tall with Window
	Floor Description	3/16", Gr 50
	Corner Post Description	7 gauge
	Under Structure Description	Crossmemberless
	Tailgate Description	18 - 36" Tall, Air Release
	Hinge Description	Dual - Greaseable
	Description of Peripheral Items (Lights, Access Steps, etc.)	FMVSS-108 Approved, Body Prop
	Is Installation included in price?	Yes ___ or No <u>X</u>
	Is Box Painted?	Yes ___ or No <u>X</u>
	Warranty Information	5 Years
	List Volume Discounts	3% 5+ Bodies
1.1	Cost for Painting box per spec	See Options Below
	TOTAL PRICE:	See Below

	Description	Answer
1.2	Wiring Standoffs	Included
	Box Options:	
1.3	12' x 100" Carbon Steel Contractor w/Fold Down Sides	\$ 12,216.00
1.4	Add for Stainless Steel Sides, Front, Gate on 12' x 100" Body	\$ 4,336.00
1.5	14' x 100" Carbon Steel Contractor w/Fold Down Sides	\$ 13,163.00
1.6	Add for Stainless Steel Sides, Front, Gate on 14' x 100" Body	\$ 4,965.00
1.7	16' x 100" Carbon Steel Contractor w/Fold Down Sides	\$ 15,357.00
1.8	Add for Stainless Steel Sides, Front, Gate on 16' x 100" Body	\$ 5,562.00
1.9	18' x 100" Carbon Steel Contractor w/Fold Down Sides	\$ 16,356.00
1.10	Add for Stainless Steel Sides, Front, Gate on 18' x 100" Body	\$ 6,159.00
	Options:	
1.11	Installation of Contractor Body	\$ 2,250.00
1.12	Painting of 12' Body - Non Metallic	\$ 2,163.00
1.13	Painting of 14' Body - Non Metallic	\$ 2,369.00
1.14	Painting of 16' Body - Non Metallic	\$ 2,575.00
1.15	Undercoating of Body	\$ 1,107.00
1.16	3/16" AR450 Floor	\$ 3,245.00
1.17	LED Lighting	\$ 375.00
1.18	Box Vibrator	\$ 1,314.00
1.19	Air Tailgate Kit, Installed	\$ 750.00
1.20	Dirt Shedding Top Rail	\$ 422.00
1.21	Coal Chute in Tailgate - Carbon Steel	\$ 762.00
1.22	Coal Chute in Tailgate - Stainless Steel	\$ 1,916.00
1.23	12" - 16" Cab Shield - Carbon Steel	\$ 896.00
1.24	12" - 16" Cab Shield - Stainless Steel	\$ 1,463.00
1.25	Doghouse w/ Front Mounted Telescopic Cylinder	\$ 777.00
1.26	Shovel Holders - Carbon Steel	\$ 181.00
1.27	10' Hook lift A-Frame 54" or 62" Hook Height Without Rollers	\$ 5,480.00
1.28	10' Hook lift A-Frame 54" or 62" Hook Height With Rollers	\$ 5,789.00
1.29	11' Hook lift A-Frame 54" or 62" Hook Height Without Rollers	\$ 6,139.00
1.30	11' Hook lift A-Frame 54" or 62" Hook Height With Rollers	\$ 6,654.00
1.31	16' Hook lift A-Frame 54" or 62" Hook Height Without Rollers	\$ 7,292.00
1.32	16' Hook lift A-Frame 54" or 62" Hook Height With Rollers	\$ 7,807.00
1.33	105 Gallon Electric 3 GPM Pre-Wet Tailgate Mount System	\$ 3,492.00
1.34	105 Gallon Hydraulic 4.5 GPM Pre-Wet Tailgate Mount System	\$ 5,577.00
1.35	Installation of Pre-Wet System	\$ 1,185.00
1.36	Sander Manifold for Hydraulic Hose Connection at Rear Pillar	\$ 537.00
1.37	24" Stainless Free Standing Cab shield w/Wiper & Steel Uprights	\$ 3,387.00
1.38	BPC Poly Fenders for Single Axle w/Mounting Kit	\$ 1,009.00
1.39	BPC Poly Fenders for Tandem Axle w/Mounting Kit	\$ 1,465.00
1.40	Pull Tarp - Up to 12'	\$ 1,427.00
1.41	Pull Tarp - Up to 16'	\$ 1,780.00
1.42	Electric Tarp w/Tension Bow	\$ 3,646.00
1.43	Warning Light Package: (12) Surface Mount LED Warning Lights, Class 1 Rated, 5 Year	\$ 1,911.00
1.44	Warning Light Package: (6) Surface Mount LED Warning Lights: Class 1 Rated, 5 Year Warranty	\$ 1,007.00
1.45	Two LED Mirror Mount Warning Lights, Class 1 Rated	\$ 845.00
1.46	Additional Set 6 1/2" Oval Cut-Out in Rear of Body: 1 Set of LED Lights	\$ 541.00
1.47	LED Flood Light, 12/24-5" Square	\$ 195.00
1.48	LED Flood Light, 12/24-6" Square	\$ 202.00
1.49	LED Class 1 Light Bar, 5 Year Warranty	\$ 541.00
1.50	Night Vision Camera w/LED Screen, Color, Heated	\$ 853.00
1.51	Additional Camera	\$ 288.00
1.52	Back-Up Alarm, Installed	\$ 499.00

	Description	
1.53	Aluminum Tool Box, Frame Mounted 18" x 18" x 18" w/ (2) Mounting Brackets	\$ 561.00
1.51	Aluminum Tool Box, Frame Mounted 18" x 18" x 24" w/ (2) Mounting Brackets	\$ 613.00
1.52	Aluminum Tool Box, Frame Mounted 18" x 18" x 36" w/ (2) Mounting Brackets	\$ 706.00
1.53	Aluminum Tool Box, Frame Mounted 18" x 18" x 48" w/ (2) Mounting Brackets	\$ 845.00
1.54	Aluminum Tool Box, Frame Mounted 18" x 18" x 60" w/ (2) Mounting Brackets	\$ 963.00
	Cost per loaded mile for pickup and or delivery of vehicle (if applicable):	\$ 4.00
	Delivery Starting Point City, State, & Zip:	
	St Cloud, MN 56304 or Fargo, ND 58078	
	Body Shop Rate	\$120.00/hr.
	Mechanic Shop Rate	\$120.00/hr.

Price quote for:	1.0 PRICE SCHEDULE DUMP BOX	
Vendor Name:	Iron Valley Equipment & Mfg. - St Cloud	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	601 Franklin Ave NE	
P.O. Box:		
City, State, Zip:	St Cloud, MN 56304	
Phone #:	320-281-3335 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Vendor Name:	Iron Valley Equipment & Mfg. - West Fargo	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	860 9th St NE Suite I	
P.O. Box:		
City, State, Zip:	West Fargo, ND 58078	
Phone #:	701-353-5226 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Item #	Information Requested	Answer
1.0	Box Make and Model	Beau-Roc SSM1
	List Truck Type Box Fits	Single Axle
	Box Style	Western Square - Stainless Steel
	Width & Length of Box	9'- 12' Long X 96" Wide
	Side Panel Description	7 Gauge SS201 2B
	Front Panel Description	7 Gauge SS201 2B
	Floor Description	3/16" Hardox 450
	Corner Post Description	Optional
	Under Structure Description	3/16" Domex 100W
	Tailgate Description	7 Gauge SS201 2B
	Hinge Description	Standard 3/4"
	Description of Peripheral Items (Lights, Access Steps, etc.)	FMVSS-108 Approved, Body Prop, Side Ladder, Hoist, Air Tailgate, LED Light Kit & Harness, Mounting
	Is Installation included in price?	Yes ___ or No <u>X</u>
	Is Box Painted?	Yes ___ or No <u>X</u>
	Warranty Information	2 Years
	List Volume Discounts	3% - 5+ Bodies
1.1	Cost for Painting box per spec	N/A
TOTAL PRICE:		See Below

	Description	Answer
1.2	Wiring Standoffs	Included
The Beau-Roc SSM1 Western Square line features ALL SS201 2B Stainless Steel bodies with Hardox 450 Floor. The combination of superior finish & Beau-Roc's durable design make this the best stainless steel body design on the market. Specifically designed for snow and ice applications as well as a variety of municipal applications where corrosion is a risk. Side features Top Rail 3" x 4" x 3/16" tubing, Board Pockets, & Ladder; Rear & Tailgate feature Double-Acting D-A banjos inst, 84" chains & shackles, air tailgate latch. Cylinders are factory installed to		
	Model SSM1 Single Axle Square Stainless	
1.3	9'; Hoist G4-80-4.25.3	\$ 24,482.00
1.4	9'6"; Hoist G4-90-4.25-3	\$ 24,781.00
1.5	10'; Hoist G4-90-4.25-3	\$ 25,008.00
1.6	10'6" Hoist G4-90-4.25-3	\$ 25,237.00
1.7	11'; Hoist G4-100-4.25-3	\$ 25,496.00
1.8	11'6" Hoist G4-100-4.25.3	\$ 25,723.00
1.9	12'; Hoist G4-110-4.25-3	\$ 26,035.00
	Options:	
1.10	Installation of Single Axle SSM1 Western Square Stainless Steel Bodies	\$ 2,685.00
1.11	Undercoating of Body	\$ 1,313.00
1.12	LED Lighting	\$ 375.00
1.13	Box Vibrator	\$ 2,344.00
1.14	12" Cab shield	\$ 646.00
1.15	10' Hook lift A-Frame 54" or 62" Hook Height Without Rollers	\$ 5,480.00
1.16	10' Hook lift A-Frame 54" or 62" Hook Height With Rollers	\$ 5,789.00
1.17	11' Hook lift A-Frame 54" or 62" Hook Height Without Rollers	\$ 6,139.00
1.18	11' Hook lift A-Frame 54" or 62" Hook Height With Rollers	\$ 6,654.00
1.19	16' Hook lift A-Frame 54" or 62" Hook Height Without Rollers	\$ 7,292.00
1.20	16' Hook lift A-Frame 54" or 62" Hook Height With Rollers	\$ 7,807.00
1.21	105 Gallon Electric 3 GPM Pre-Wet Tailgate Mount System	\$ 3,492.00
1.22	105 Gallon Hydraulic 4.5 GPM Pre-Wet Tailgate Mount System	\$ 5,577.00
1.23	Installation of Pre-Wet System	\$ 1,185.00
1.24	BPC Poly Fenders for Single Axle w/Mounting Kit	\$ 1,009.00
1.25	Pull Tarp - Up to 12'	\$ 1,427.00
1.26	Pull Tarp - Up to 16'	\$ 1,780.00
1.27	Electric Tarp w/Tension Bow	\$ 3,646.00
1.28	Warning Light Package: (12) Surface Mount LED Warning Lights, Class 1 Rated, 5 Year	\$ 1,911.00
1.29	Warning Light Package: (6) Surface Mount LED Warning Lights: Class 1 Rated, 5 Year	\$ 1,007.00
1.30	Two LED Mirror Mount Warning Lights, Class 1 Rated	\$ 845.00
1.31	Additional Set 6 1/2" Oval Cut-Out in Rear of Body: 1 Set of LED Lights	\$ 541.00
1.32	LED Flood Light, 12/24-5" Square	\$ 195.00
1.33	LED Flood Light, 12/24-6" Square	\$ 202.00
1.34	LED Class 1 Light Bar, 5 Year Warranty	\$ 541.00
1.35	Night Vision Camera w/LED Screen, Color, Heated	\$ 1,059.00
1.36	Additional Camera	\$ 391.00
1.37	Back-Up Alarm, Installed	\$ 499.00
1.38	Aluminum Tool Box, Frame Mounted 18" x 18" x 18" w/ (2) Mounting Brackets	\$ 561.00
1.39	Aluminum Tool Box, Frame Mounted 18" x 18" x 24" w/ (2) Mounting Brackets	\$ 613.00
	Description	
1.40	Aluminum Tool Box, Frame Mounted 18" x 18" x 36" w/ (2) Mounting Brackets	\$ 706.00
1.41	Aluminum Tool Box, Frame Mounted 18" x 18" x 48" w/ (2) Mounting Brackets	\$ 845.00
1.42	Aluminum Tool Box, Frame Mounted 18" x 18" x 60" w/ (2) Mounting Brackets	\$ 963.00
	Cost per loaded mile for pickup and or delivery of vehicle (if applicable):	\$ 4.00
	Delivery Starting Point City, State, & Zip:	
	St Cloud, MN 56304 or Fargo, ND 58078	
	Body Shop Rate	\$120.00/hr.
	Mechanic Shop Rate	\$120.00/hr.

Price quote for:	1.0 PRICE SCHEDULE DUMP BOX	
Vendor Name:	Iron Valley Equipment & Mfg. - St Cloud	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	601 Franklin Ave NE	
P.O. Box:		
City, State, Zip:	St Cloud, MN 56304	
Phone #:	320-281-3335 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Vendor Name:	Iron Valley Equipment & Mfg. - West Fargo	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	860 9th St NE Suite I	
P.O. Box:		
City, State, Zip:	West Fargo, ND 58078	
Phone #:	701-353-5226 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Item #	Information Requested	Answer
1.0	Box Make and Model	Beau-Roc SSM1
	List Truck Type Box Fits	Tandem Axle
	Box Style	Western Square - Stainless Steel
	Width & Length of Box	14' - 15'6" Long X 96" Wide
	Side Panel Description	7 Gauge SS201 2B
	Front Panel Description	7 Gauge SS201 2B
	Floor Description	3/16" Hardox 450
	Corner Post Description	Optional
	Under Structure Description	3/16" Domex 100W
	Tailgate Description	7 Gauge SS201 2B
	Hinge Description	Standard 3/4"
	Description of Peripheral Items (Lights, Access Steps, etc.)	FMVSS-108 Approved, Body Prop, Side Ladder, Hoist, Air Tailgate, LED Light Kit & Harness, Mounting
	Is Installation included in price?	Yes or No X
	Is Box Painted?	Yes or No X
	Warranty Information	2 Years
	List Volume Discounts	3% - 5+ Bodies
1.1	Cost for Painting box per spec	N/A
	TOTAL PRICE:	See Below

	Description	Answer
1.2	Wiring Standoffs	Included
The Beau-Roc SSM1 Western Square line features ALL SS201 2B Stainless Steel bodies with Hardox 450 Floor. The combination of superior finish & Beau-Roc's durable design make this the best stainless steel body design on the market. Specifically designed for snow and ice applications as well as a variety of municipal applications where corrosion is a risk. Side features Top Rail 3" x 4" x 3/16" tubing, Board Pockets, & Ladder; Rear & Tailgate feature Double-Acting D-A banjos inst, 84" chains & shackles, air tailgate latch. Cylinders are factory installed to bodies at Mfg. Facility.		
Model DHS Tandem Square Stainless		
1.3	14'; Hoist G4-80-4.25-3	\$ 27,589.00
1.4	14'6"; Hoist G4-90-4.25-3	\$ 27,921.00
1.5	15'; Hoist G4-90-4.25-3	\$ 28,251.00
1.6	15'6"; Hoist G4-90-4.25-3	\$ 28,826.00
Options:		
1.7	Installation of Tandem Axle SSM1 Western Square Stainless Steel Bodies	\$ 3,985.00
1.8	Undercoating of Body	\$ 2,009.00
1.9	LED Lighting	\$ 375.00
1.10	Box Vibrator	\$ 3,261.00
1.11	12" Cab shield	\$ 691.00
1.12	16' Hook lift A-Frame 54" or 62" Hook Height Without Rollers	\$ 7,292.00
1.13	16' Hook lift A-Frame 54" or 62" Hook Height With Rollers	\$ 7,807.00
1.14	105 Gallon Electric 3 GPM Pre-Wet Tailgate Mount System	\$ 3,492.00
1.15	105 Gallon Hydraulic 4.5 GPM Pre-Wet Tailgate Mount System	\$ 5,577.00
1.16	Installation of Pre-Wet System	\$ 1,185.00
1.17	BPC Poly Fenders for Tandem Axle w/Mounting Kit	\$ 1,465.00
1.18	Pull Tarp - Up to 16'	\$ 1,780.00
1.19	Electric Tarp w/Tension Bow	\$ 3,646.00
1.20	Warning Light Package: (12) Surface Mount LED Warning Lights, Class 1 Rated, 5 Year Warranty	\$ 1,911.00
1.21	Warning Light Package: (6) Surface Mount LED Warning Lights: Class 1 Rated, 5 Year Warranty	\$ 1,007.00
1.22	Two LED Mirror Mount Warning Lights, Class 1 Rated	\$ 845.00
1.23	Additional Set 6 1/2" Oval Cut-Out in Rear of Body: 1 Set of LED Lights	\$ 541.00
1.24	LED Flood Light, 12/24-5" Square	\$ 195.00
1.25	LED Flood Light, 12/24-6" Square	\$ 202.00
1.26	LED Class 1 Light Bar, 5 Year Warranty	\$ 541.00
1.27	Night Vision Camera w/LED Screen, Color, Heated	\$ 1,059.00
1.28	Additional Camera	\$ 391.00
1.29	Back-Up Alarm, Installed	\$ 499.00
1.30	Aluminum Tool Box, Frame Mounted 18" x 18" x 18" w/ (2) Mounting Brackets	\$ 561.00
1.31	Aluminum Tool Box, Frame Mounted 18" x 18" x 24" w/ (2) Mounting Brackets	\$ 613.00
1.32	Aluminum Tool Box, Frame Mounted 18" x 18" x 36" w/ (2) Mounting Brackets	\$ 706.00
1.33	Aluminum Tool Box, Frame Mounted 18" x 18" x 48" w/ (2) Mounting Brackets	\$ 845.00
1.34	Aluminum Tool Box, Frame Mounted 18" x 18" x 60" w/ (2) Mounting Brackets	\$ 963.00
Cost per loaded mile for pickup and or delivery of vehicle (if applicable):		\$ 4.00
Delivery Starting Point City, State, & Zip:		
St Cloud, MN 56304 or Fargo, ND 58078		
Body Shop Rate		\$120.00/hr.
Mechanic Shop Rate		\$120.00/hr.

Price quote for:	1.0 PRICE SCHEDULE DUMP BOX	
Vendor Name:	Iron Valley Equipment & Mfg. - St Cloud	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	601 Franklin Ave NE	
P.O. Box:		
City, State, Zip:	St Cloud, MN 56304	
Phone #:	320-281-3335 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Vendor Name:	Iron Valley Equipment & Mfg. - West Fargo	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	860 9th St NE Suite I	
P.O. Box:		
City, State, Zip:	West Fargo, ND 58078	
Phone #:	701-353-5226 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Item #	Information Requested	Answer
1.0	Box Make and Model	Beau-Roc SSM1
	List Truck Type Box Fits	Tri Axle - Quad Axle
	Box Style	Western Square - Stainless Steel
	Width & Length of Box	16' - 18' Long X 96" Wide
	Side Panel Description	7 Gauge SS201 2B
	Front Panel Description	7 Gauge SS201 2B
	Floor Description	3/16" Hardox 450
	Corner Post Description	Optional
	Under Structure Description	3/16" Domex 100W
	Tailgate Description	7 Gauge SS201 2B
	Hinge Description	Standard 3/4"
	Description of Peripheral Items (Lights, Access Steps, etc.)	FMVSS-108 Approved, Body Prop, Side Ladder, Hoist, Air Tailgate, LED Light Kit & Harness, Mounting
	Is Installation included in price?	Yes ___ or No X ___
	Is Box Painted?	Yes ___ or No X ___
	Warranty Information	2 Years
	List Volume Discounts	3% - 5+ Bodies
1.1	Cost for Painting box per spec	N/A
	TOTAL PRICE:	See Below

	Description	Answer
1.2	Wiring Standoffs	Included
<p>The Beau-Roc SSM1 Western Square line features ALL SS201 2B Stainless Steel bodies with Hardox 450 Floor. The combination of superior finish & Beau-Roc's durable design make this the best stainless steel body design on the market. Specifically designed for snow and ice applications as well as a variety of municipal applications where corrosion is a risk. Side features Top Rail 3" x 4" x 3/16" tubing, Board Pockets, & Ladder; Rear & Tailgate feature Double-Acting D-A banjos inst, 84" chains & shackles, air tailgate latch. Cylinders are factory installed to bodies at Mfg. Facility.</p>		
Model DL Tri - Quad Axle Square Stainless		
1.3	16'; Sill Height 8"; Hoist G4-135-5.7-4	\$ 32,213.00
1.4	16'6"; Sill Height 8"; Hoist G4-150-5.7-4	\$ 33,331.00
1.5	17'; Sill Height 8"; Hoist G4-150-5.7-4	\$ 33,565.00
1.6	17'6"; Sill Height 8" Hoist G4-160-5.7-4	\$ 33,852.00
1.7	18'; Sill Height 10"; Hoist G4-160-5.7-4	\$ 34,481.00
Add for 1/4" Hardox450 Floor		
1.80	16'; Sill Height 8"; Hoist G3-150-5.7-4	\$ 852.00
1.9	16'6"; Sill Height 8"; Hoist G3-150-5.7-4	\$ 1,005.00
1.10	17'; Sill Height 8"; Hoist G3-150-5.7-4	\$ 1,159.00
1.11	17'6"; Sill Height 8" Hoist G3-160-5.7-4	\$ 1,444.00
1.12	18'; Sill Height 10"; Hoist G3-160-5.7-4	\$ 1,718.00
1.13	18'6"; Sill Height 10"; Hoist G3-170-5.7-4	\$ 1,976.00
1.14	19'; Sill Height 10"; Hoist G3-170-5.7-4	\$ 2,233.00
Options:		
1.15	Installation of Tri Axle - Quad Axle SSM1 Western Square Stainless Steel Bodies	\$ 4,285.00
1.16	Undercoating of Body	\$ 2,009.00
1.17	LED Lighting	\$ 375.00
1.18	Box Vibrator	\$ 3,570.00
1.19	12" Cab shield	\$ 646.00
1.20	Internal Air High Lift	\$ 3,589.00
1.21	105 Gallon Electric 3 GPM Pre-Wet Tailgate Mount System	\$ 3,492.00
1.22	105 Gallon Hydraulic 4.5 GPM Pre-Wet Tailgate Mount System	\$ 5,577.00
1.23	Installation of Pre-Wet System	\$ 1,185.00
1.24	Warning Light Package: (12) Surface Mount LED Warning Lights, Class 1 Rated, 5 Year Warranty	\$ 1,911.00
1.25	Warning Light Package: (6) Surface Mount LED Warning Lights: Class 1 Rated, 5 Year Warranty	\$ 1,007.00
1.26	Two LED Mirror Mount Warning Lights, Class 1 Rated	\$ 845.00
1.27	Additional Set 6 1/2" Oval Cut-Out in Rear of Body: 1 Set of LED Lights	\$ 541.00
1.28	LED Flood Light, 12/24-5" Square	\$ 195.00
1.29	LED Flood Light, 12/24-6" Square	\$ 202.00
1.30	LED Class 1 Light Bar, 5 Year Warranty	\$ 541.00
1.31	Night Vision Camera w/LED Screen, Color, Heated	\$ 1,059.00
1.32	Additional Camera	\$ 391.00
1.33	Back-Up Alarm, Installed	\$ 499.00
1.34	Aluminum Tool Box, Frame Mounted 18" x 18" x 18" w/ (2) Mounting Brackets	\$ 561.00
1.35	Aluminum Tool Box, Frame Mounted 18" x 18" x 24" w/ (2) Mounting Brackets	\$ 613.00
1.36	Aluminum Tool Box, Frame Mounted 18" x 18" x 36" w/ (2) Mounting Brackets	\$ 706.00
1.37	Aluminum Tool Box, Frame Mounted 18" x 18" x 48" w/ (2) Mounting Brackets	\$ 845.00
1.38	Aluminum Tool Box, Frame Mounted 18" x 18" x 60" w/ (2) Mounting Brackets	\$ 963.00
	Cost per loaded mile for pickup and or delivery of vehicle (if applicable):	\$ 4.00
	Delivery Starting Point City, State, & Zip:	
	St Cloud, MN 56304 or Fargo, ND 58078	
	Body Shop Rate	\$120.00/hr.
	Mechanic Shop Rate	\$120.00/hr.

Price quote for:	1.0 PRICE SCHEDULE DUMP BOX	
Vendor Name:	Iron Valley Equipment & Mfg. - St Cloud	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	601 Franklin Ave NE	
P.O. Box:		
City, State, Zip:	St Cloud, MN 56304	
Phone #:	320-281-3335 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Vendor Name:	Iron Valley Equipment & Mfg. - West Fargo	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	860 9th St NE Suite I	
P.O. Box:		
City, State, Zip:	West Fargo, ND 58078	
Phone #:	701-353-5226 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Item #	Information Requested	Answer
1.0	Box Make and Model	Beau-Roc Diamond DL
	List Truck Type Box Fits	Tri - Quad Axle
	Box Style	Western Square - Steel
	Width & Length of Box	16' - 18' Long X 96" Wide
	Side Panel Description	Hardox 450
	Front Panel Description	Hardox 450
	Floor Description	3/16" Hardox 450
	Corner Post Description	None
	Under Structure Description	3/16" Domex 100W
	Tailgate Description	48" Hardox 450
	Hinge Description	HD Slanted 1"
	Description of Peripheral Items (Lights, Access Steps, etc.)	FMVSS-108 Approved, Body Prop, Side Ladder, Hoist, Air Tailgate, LED Light Kit & Harness, Mounting
	Is Installation included in price?	Yes___ or No_X__
	Is Box Painted?	Yes___ or No_X__
	Warranty Information	2 Years
	List Volume Discounts	3% - 5+ Bodies
1.1	Cost for Painting box per spec	See Options Below
	TOTAL PRICE:	See Below

	Description	Answer
1.2	Wiring Standoffs	Included
The Beau-Roc Diamond DHS Western Square line features ALL Hardox bodies. Recommended for a wide range of applications from high volume materials (sand, gravel, asphalt, dirt, etc.) to occasional heavier-duty applications. Well suited for everyday heavy-duty applications such as concrete & large rock. Top Rail 3" x 4" x 3/16" tubing, Board Pockets, & Ladder; Rear & Tailgate feature 48" chains & shackles, air tailgate latch. Cylinders are factory installed to bodies at Mfg. facility.		
Model DL Tri - Quad Axle Square Steel		
1.3	16'; Sill Height 8"; Hoist G3-150-5.7-4	\$ 25,705.00
1.4	16'6"; Sill Height 8"; Hoist G3-150-5.7-4	\$ 25,853.00
1.5	17'; Sill Height 8"; Hoist G3-150-5.7-4	\$ 26,661.00
1.6	17'6"; Sill Height 8" Hoist G3-160-5.7-4	\$ 27,006.00
1.7	18'; Sill Height 10"; Hoist G3-160-5.7-4	\$ 27,386.00
Add for 1/4" Hardox450 Floor		
1.8	16'; Sill Height 8"; Hoist G3-150-5.7-4	\$ 852.00
1.9	16'6"; Sill Height 8"; Hoist G3-150-5.7-4	\$ 1,005.00
1.10	17'; Sill Height 8"; Hoist G3-150-5.7-4	\$ 1,159.00
1.11	17'6"; Sill Height 8" Hoist G3-160-5.7-4	\$ 1,444.00
1.12	18'; Sill Height 10"; Hoist G3-160-5.7-4	\$ 1,718.00
Options:		
1.13	Installation of Tri - Quad Axle DL Square Steel Bodies	\$ 3,985.00
1.14	Painting of 16' Body - Non Metallic	\$ 3,713.00
1.15	Painting of 16'6" Body - Non Metallic	\$ 3,940.00
1.16	Painting of 17' Body - Non Metallic	\$ 4,002.00
1.17	Painting of 17'6" Body - Non Metallic	\$ 4,063.00
1.18	Painting of 18' Body - Non Metallic	\$ 4,120.00
1.19	Undercoating of Body	\$ 2,009.00
1.20	LED Lighting	\$ 375.00
1.21	Box Vibrator	\$ 3,570.00
1.22	12" Cab shield	\$ 646.00
1.23	Internal Air High Lift	\$ 3,383.00
1.24	105 Gallon Electric 3 GPM Pre-Wet Tailgate Mount System	\$ 3,492.00
1.25	105 Gallon Hydraulic 4.5 GPM Pre-Wet Tailgate Mount System	\$ 5,577.00
1.26	Installation of Pre-Wet System	\$ 1,185.00
1.27	Warning Light Package: (12) Surface Mount LED Warning Lights, Class 1 Rated, 5 Year	\$ 1,911.00
1.28	Warning Light Package: (6) Surface Mount LED Warning Lights: Class 1 Rated, 5 Year Warranty	\$ 1,007.00
1.29	Two LED Mirror Mount Warning Lights, Class 1 Rated	\$ 845.00
1.30	Additional Set 6 1/2" Oval Cut-Out in Rear of Body: 1 Set of LED Lights	\$ 541.00
1.31	LED Flood Light, 12/24-5" Square	\$ 195.00
1.32	LED Flood Light, 12/24-6" Square	\$ 202.00
1.33	LED Class 1 Light Bar, 5 Year Warranty	\$ 541.00
1.34	Night Vision Camera w/LED Screen, Color, Heated	\$ 1,059.00
1.35	Additional Camera	\$ 391.00
1.36	Back-Up Alarm, Installed	\$ 499.00
1.37	Aluminum Tool Box, Frame Mounted 18" x 18" x 18" w/ (2) Mounting Brackets	\$ 561.00
1.38	Aluminum Tool Box, Frame Mounted 18" x 18" x 24" w/ (2) Mounting Brackets	\$ 613.00
1.39	Aluminum Tool Box, Frame Mounted 18" x 18" x 36" w/ (2) Mounting Brackets	\$ 706.00
1.40	Aluminum Tool Box, Frame Mounted 18" x 18" x 48" w/ (2) Mounting Brackets	\$ 845.00
1.41	Aluminum Tool Box, Frame Mounted 18" x 18" x 60" w/ (2) Mounting Brackets	\$ 963.00
	Cost per loaded mile for pickup and or delivery of vehicle (if applicable):	\$ 4.00
	Delivery Starting Point City, State, & Zip:	
	St Cloud, MN 56304 or Fargo, ND 58078	
	Body Shop Rate	\$120.00/hr.
	Mechanic Shop Rate	\$120.00/hr.

Price quote for:	1.0 PRICE SCHEDULE DUMP BOX	
Vendor Name:	Iron Valley Equipment & Mfg. - St Cloud	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	601 Franklin Ave NE	
P.O. Box:		
City, State, Zip:	St Cloud, MN 56304	
Phone #:	320-281-3335 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Vendor Name:	Iron Valley Equipment & Mfg. - West Fargo	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	860 9th St NE Suite I	
P.O. Box:		
City, State, Zip:	West Fargo, ND 58078	
Phone #:	701-353-5226 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Item #	Information Requested	Answer
1.0	Box Make and Model	Beau-Roc Diamond DHS
	List Truck Type Box Fits	Single Axle
	Box Style	Western Square - Steel
	Width & Length of Box	9'- 12' Long X 96" Wide
	Side Panel Description	Hardox 450
	Front Panel Description	Hardox 450
	Floor Description	3/16" Hardox 450
	Corner Post Description	None
	Under Structure Description	3/16" 44-W
	Tailgate Description	42" Hardox 450
	Hinge Description	Standard 3/4"
	Description of Peripheral Items (Lights, Access Steps, etc.)	FMVSS-108 Approved, Body Prop, Side Ladder, Hoist, Air Tailgate, LED Light Kit & Harness,
	Is Installation included in price?	Yes ___ or No <u>X</u>
	Is Box Painted?	Yes ___ or No <u>X</u>
	Warranty Information	2 Years
	List Volume Discounts	3% - 5+ Bodies
1.1	Cost for Painting box per spec	
	TOTAL PRICE:	See Below

	Description	Answer
1.2	Wiring Standoffs	Included
The Beau-Roc Diamond DHS Western Square line features ALL Hardox bodies. Recommended for light materials hauling such as sand, dirt, and gravel as well as a wide range of municipal applications. Top Rail 3" x 4" x 3/16" tubing, Board Pockets, & Ladder; Rear & Tailgate feature Double-Acting D-A banjos inst, 84" chains & shackles, air tailgate latch. Cylinders are factory installed to bodies at Mfg. facility.		
	Model DHS Single Axle Square Steel	
1.3	9'; Hoist G3-90-4.25-3	\$ 16,551.00
1.4	9'6"; Hoist G3-90-4.25-3	\$ 16,777.00
1.5	10'; Hoist G3-90-4.25-3	\$ 17,087.00
1.6	10'6" Hoist G3-90-4.25-3	\$ 17,232.00
1.7	11'; Hoist G3-100-4.25-3	\$ 17,592.00
1.8	11'6" Hoist G3-100-4.25-3	\$ 17,775.00
1.9	12'; Hoist G3-110-4.25-3	\$ 18,103.00
	Options:	
1.10	Installation of Single Axle DHS Western Square Steel Bodies	\$ 2,485.00
1.11	Painting of 9' Body - Non Metallic	\$ 2,627.00
1.12	Painting of 9'6" Body - Non Metallic	\$ 2,833.00
1.13	Painting of 10' Body - Non Metallic	\$ 3,039.00
1.14	Painting of 10'6" Body - Non Metallic	\$ 3,142.00
1.15	Painting of 11' Body - Non Metallic	\$ 3,245.00
1.16	Painting of 11'6" Body - Non Metallic	\$ 3,348.00
1.17	Painting of 12' Body - Non Metallic	\$ 3,451.00
1.18	Undercoating of Body	\$ 1,313.00
1.19	LED Lighting	\$ 375.00
1.20	Box Vibrator	\$ 2,344.00
1.21	12" Cab shield	\$ 377.00
1.22	10' Hook lift A-Frame 54" or 62" Hook Height Without Rollers	\$ 5,480.00
1.23	10' Hook lift A-Frame 54" or 62" Hook Height With Rollers	\$ 5,789.00
1.24	11' Hook lift A-Frame 54" or 62" Hook Height Without Rollers	\$ 6,139.00
1.25	11' Hook lift A-Frame 54" or 62" Hook Height With Rollers	\$ 6,654.00
1.26	16' Hook lift A-Frame 54" or 62" Hook Height Without Rollers	\$ 7,292.00
1.27	16' Hook lift A-Frame 54" or 62" Hook Height With Rollers	\$ 7,807.00
1.28	105 Gallon Electric 3 GPM Pre-Wet Tailgate Mount System	\$ 3,492.00
1.29	105 Gallon Hydraulic 4.5 GPM Pre-Wet Tailgate Mount System	\$ 5,577.00
1.30	Installation of Pre-Wet System	\$ 1,185.00
1.31	BPC Poly Fenders for Single Axle w/Mounting Kit	\$ 1,009.00
1.32	Pull Tarp - Up to 12'	\$ 1,427.00
1.33	Pull Tarp - Up to 16'	\$ 1,780.00
1.34	Electric Tarp w/Tension Bow	\$ 3,646.00
1.35	Warning Light Package: (12) Surface Mount LED Warning Lights, Class 1 Rated, 5 Year	\$ 1,911.00
1.36	Warning Light Package: (6) Surface Mount LED Warning Lights: Class 1 Rated, 5 Year Warranty	\$ 1,007.00
1.37	Two LED Mirror Mount Warning Lights, Class 1 Rated	\$ 845.00
1.38	Additional Set 6 1/2" Oval Cut-Out in Rear of Body: 1 Set of LED Lights	\$ 541.00
1.39	LED Flood Light, 12/24-5" Square	\$ 195.00
1.40	LED Flood Light, 12/24-6" Square	\$ 202.00
1.41	LED Class 1 Light Bar, 5 Year Warranty	\$ 541.00
1.42	Night Vision Camera w/LED Screen, Color, Heated	\$ 1,059.00
1.43	Additional Camera	\$ 391.00
1.44	Back-Up Alarm, Installed	\$ 499.00
	Description	
1.45	Aluminum Tool Box, Frame Mounted 18" x 18" x 18" w/ (2) Mounting Brackets	\$ 561.00
1.46	Aluminum Tool Box, Frame Mounted 18" x 18" x 24" w/ (2) Mounting Brackets	\$ 613.00
1.47	Aluminum Tool Box, Frame Mounted 18" x 18" x 36" w/ (2) Mounting Brackets	\$ 706.00
1.48	Aluminum Tool Box, Frame Mounted 18" x 18" x 48" w/ (2) Mounting Brackets	\$ 845.00
1.49	Aluminum Tool Box, Frame Mounted 18" x 18" x 60" w/ (2) Mounting Brackets	\$ 963.00
	Cost per loaded mile for pickup and or delivery of vehicle (if applicable):	\$ 4.00
	Delivery Starting Point City, State, & Zip:	
	St Cloud, MN 56304 or Fargo, ND 58078	
	Body Shop Rate	\$120.00/hr.
	Mechanic Shop Rate	\$120.00/hr.

Price quote for:	1.0 PRICE SCHEDULE DUMP BOX	
Vendor Name:	Iron Valley Equipment & Mfg. - St Cloud	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	601 Franklin Ave NE	
P.O. Box:		
City, State, Zip:	St Cloud, MN 56304	
Phone #:	320-281-3335 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Vendor Name:	Iron Valley Equipment & Mfg. - West Fargo	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	860 9th St NE Suite I	
P.O. Box:		
City, State, Zip:	West Fargo, ND 58078	
Phone #:	701-353-5226 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Item #	Information Requested	Answer
1.0	Box Make and Model	Beau-Roc Diamond DHS
	List Truck Type Box Fits	Tandem Axle
	Box Style	Western Square - Steel
	Width & Length of Box	14' - 15'6" Long X 96" Wide
	Side Panel Description	Hardox 450
	Front Panel Description	Hardox 450
	Floor Description	3/16" Hardox 450
	Corner Post Description	None
	Under Structure Description	3/16" 44-W
	Tailgate Description	42" Hardox 450
	Hinge Description	Standard 3/4"
	Description of Peripheral Items (Lights, Access Steps, etc.)	FMVSS-108 Approved, Body Prop, Side Ladder, Hoist, Air Tailgate, LED Light Kit & Harness,
	Is Installation included in price?	Yes <input type="checkbox"/> or No <input checked="" type="checkbox"/>
	Is Box Painted?	Yes <input type="checkbox"/> or No <input checked="" type="checkbox"/>
	Warranty Information	2 Years
	List Volume Discounts	3% - 5+ Bodies
1.1	Cost for Painting box per spec	
	TOTAL PRICE:	See Below

	Description	Answer
1.2	Wiring Standoffs	Included
The Beau-Roc Diamond DHS Western Square line features ALL Hardox bodies. Recommended for light materials hauling such as sand, dirt, and gravel as well as a wide range of municipal applications. Top Rail 3" x 4" x 3/16" tubing, Board Pockets, & Ladder; Rear & Tailgate feature Double-Acting D-A banjos inst, 84" chains & shackles, air tailgate latch. Cylinders are factory installed to bodies at Mfg. Facility.		
Model DHS Tandem Square Steel		
1.3	14'; Hoist G3-130-5-3	\$ 20,527.00
1.4	14'6"; Hoist G3-130-5-3	\$ 21,030.00
1.5	15'; Hoist G3-140-5-3	\$ 21,400.00
1.6	15'6"; Hoist G3-140-5-3	\$ 21,940.00
Options:		
1.7	Installation of Tandem Axle DHS Square Steel Bodies	\$ 3,985.00
1.8	Undercoating of Body	\$ 2,009.00
1.9	LED Lighting	\$ 375.00
1.10	Box Vibrator	\$ 3,261.00
1.11	12" Cab shield	\$ 691.00
1.12	16' Hook lift A-Frame 54" or 62" Hook Height Without Rollers	\$ 7,292.00
1.13	16' Hook lift A-Frame 54" or 62" Hook Height With Rollers	\$ 7,807.00
1.14	105 Gallon Electric 3 GPM Pre-Wet Tailgate Mount System	\$ 3,492.00
1.15	105 Gallon Hydraulic 4.5 GPM Pre-Wet Tailgate Mount System	\$ 5,577.00
1.16	Installation of Pre-Wet System	\$ 1,185.00
1.17	BPC Poly Fenders for Tandem Axle w/Mounting Kit	\$ 1,465.00
1.18	Pull Tarp - Up to 16'	\$ 1,780.00
1.19	Electric Tarp w/Tension Bow	\$ 3,646.00
1.20	Warning Light Package: (12) Surface Mount LED Warning Lights, Class 1 Rated, 5 Year	\$ 1,911.00
1.21	Warning Light Package: (6) Surface Mount LED Warning Lights: Class 1 Rated, 5 Year	\$ 1,007.00
1.22	Two LED Mirror Mount Warning Lights, Class 1 Rated	\$ 845.00
1.23	Additional Set 6 1/2" Oval Cut-Out in Rear of Body: 1 Set of LED Lights	\$ 541.00
1.24	LED Flood Light, 12/24-5" Square	\$ 195.00
1.25	LED Flood Light, 12/24-6" Square	\$ 202.00
1.26	LED Class 1 Light Bar, 5 Year Warranty	\$ 541.00
1.27	Night Vision Camera w/LED Screen, Color, Heated	\$ 1,059.00
1.28	Additional Camera	\$ 391.00
1.29	Back-Up Alarm, Installed	\$ 499.00
1.30	Aluminum Tool Box, Frame Mounted 18" x 18" x 18" w/ (2) Mounting Brackets	\$ 561.00
1.31	Aluminum Tool Box, Frame Mounted 18" x 18" x 24" w/ (2) Mounting Brackets	\$ 613.00
1.32	Aluminum Tool Box, Frame Mounted 18" x 18" x 36" w/ (2) Mounting Brackets	\$ 706.00
1.33	Aluminum Tool Box, Frame Mounted 18" x 18" x 48" w/ (2) Mounting Brackets	\$ 845.00
1.34	Aluminum Tool Box, Frame Mounted 18" x 18" x 60" w/ (2) Mounting Brackets	\$ 963.00
Cost per loaded mile for pickup and or delivery of vehicle (if applicable):		\$ 4.00
Delivery Starting Point City, State, & Zip:		
St Cloud, MN 56304 or Fargo, ND 58078		
Body Shop Rate		\$120.00/hr.
Mechanic Shop Rate		\$120.00/hr.

Price quote for:	1.0 PRICE SCHEDULE DUMP BOX	
Vendor Name:	Iron Valley Equipment & Mfg. - St Cloud	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	601 Franklin Ave NE	
P.O. Box:		
City, State, Zip:	St Cloud, MN 56304	
Phone #:	320-281-3335 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Vendor Name:	Iron Valley Equipment & Mfg. - West Fargo	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	860 9th St NE Suite I	
P.O. Box:		
City, State, Zip:	West Fargo, ND 58078	
Phone #:	701-353-5226 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Item #	Information Requested	Answer
1.0	Box Make and Model	Beau-Roc Diamond RXL
	List Truck Type Box Fits	Single Axle
	Box Style	Elliptical - Steel
	Width & Length of Box	9'- 12' Long X 96" Wide
	Side Panel Description	Hardox 450
	Front Panel Description	Hardox 450
	Floor Description	3/16" Hardox 450
	Corner Post Description	None
	Under Structure Description	1/4" 44-W
	Tailgate Description	42" Hardox 450
	Hinge Description	Standard 3/4"
	Description of Peripheral Items (Lights, Access Steps, etc.)	FMVSS-108 Approved, Body Prop, Side Ladder, Hoist, Air Tailgate, LED Light Kit & Harness, Mounting Kit
	Is Installation included in price?	Yes ___ or No X ___
	Is Box Painted?	Yes ___ or No X ___
	Warranty Information	2 Years
	List Volume Discounts	3% 5+ Bodies
1.1	Cost for Painting box per spec	See Options Below
	TOTAL PRICE:	See Below

	Description	Answer
1.2	Wiring Standoffs	Included
The Beau-Roc Diamond RXL Elliptical line features ALL Hardox bodies. Recommended for a wide range of applications from light materials hauling (sand, gravel, dirt, asphalt, etc.) to super-duty applications such as concrete, large rock & quarry work. Side features Top Rail 4" x 4" x 3/16" tubing, Board Pockets, & Ladder; Rear & Tailgate feature Double-Acting D-A banjos inst, 84" chains & shackles, air tailgate latch. Cylinders are factory installed to bodies at Mfg. Facility.		
Model RXL Single Axle Elliptical Steel		
1.3	Length 9'; Hoist G3-90-4.25-3	\$ 16,439.00
1.4	Length 9'6"; Hoist G3-90-4.25-3	\$ 16,674.00
1.5	Length 10'; Hoist G3-90-4.25-3	\$ 16,908.00
1.6	Length 10'6"; Hoist G3-90-4.25-3	\$ 17,143.00
1.7	Length 11'; Hoist G3-100-4.25-3	\$ 17,457.00
1.8	Length 11'6"; Hoist G3-100-4.25-3	\$ 17,830.00
1.9	Length 12'; Hoist G3-110-4.25-3	\$ 18,092.00
Options:		
1.10	Installation of Single Axle RXL Elliptical Steel Bodies	\$ 2,560.00
1.11	Painting of 9' Body - Non Metallic	\$ 2,627.00
1.12	Painting of 9'6" Body - Non Metallic	\$ 2,833.00
1.13	Painting of 10' Body - Non Metallic	\$ 3,039.00
1.14	Painting of 10'6" Body - Non Metallic	\$ 3,142.00
1.15	Painting of 11' Body - Non Metallic	\$ 3,245.00
1.16	Painting of 11'6' Body - Non Metallic	\$ 3,348.00
1.17	Painting of 12' Body - Non Metallic	\$ 3,451.00
1.18	Undercoating of Body	\$ 1,313.00
1.19	LED Lighting	\$ 375.00
1.2	Box Vibrator	\$ 2,344.00
1.21	12" Cab shield	\$ 377.00
1.22	10' Hook lift A-Frame 54" or 62" Hook Height Without Rollers	\$ 5,480.00
1.23	10' Hook lift A-Frame 54" or 62" Hook Height With Rollers	\$ 5,789.00
1.24	11' Hook lift A-Frame 54" or 62" Hook Height Without Rollers	\$ 6,139.00
1.25	11' Hook lift A-Frame 54" or 62" Hook Height With Rollers	\$ 6,654.00
1.26	16' Hook lift A-Frame 54" or 62" Hook Height Without Rollers	\$ 7,292.00
1.27	16' Hook lift A-Frame 54" or 62" Hook Height With Rollers	\$ 7,807.00
1.28	105 Gallon Electric 3 GPM Pre-Wet Tailgate Mount System	\$ 3,492.00
1.29	105 Gallon Hydraulic 4.5 GPM Pre-Wet Tailgate Mount System	\$ 5,577.00
1.3	Installation of Pre-Wet System	\$ 1,185.00
1.31	BPC Poly Fenders for Single Axle w/Mounting Kit	\$ 1,009.00
1.32	Pull Tarp - Up to 12'	\$ 1,427.00
1.33	Pull Tarp - Up to 16'	\$ 1,780.00
1.34	Electric Tarp w/Tension Bow	\$ 3,646.00
1.35	Warning Light Package: (12) Surface Mount LED Warning Lights, Class 1 Rated, 5 Year	\$ 1,911.00
1.36	Warning Light Package: (6) Surface Mount LED Warning Lights: Class 1 Rated, 5 Year	\$ 1,007.00
1.37	Two LED Mirror Mount Warning Lights, Class 1 Rated	\$ 845.00
1.38	Additional Set 6 1/2" Oval Cut-Out in Rear of Body: 1 Set of LED Lights	\$ 541.00
1.39	LED Flood Light, 12/24-5" Square	\$ 195.00
1.4	LED Flood Light, 12/24-6" Square	\$ 202.00
1.41	LED Class 1 Light Bar, 5 Year Warranty	\$ 541.00
1.42	Night Vision Camera w/LED Screen, Color, Heated	\$ 1,059.00
1.43	Additional Camera	\$ 391.00
1.44	Back-Up Alarm, Installed	\$ 499.00
1.45	Aluminum Tool Box, Frame Mounted 18" x 18" x 18" w/ (2) Mounting Brackets	\$ 561.00
1.46	Aluminum Tool Box, Frame Mounted 18" x 18" x 24" w/ (2) Mounting Brackets	\$ 613.00
1.47	Aluminum Tool Box, Frame Mounted 18" x 18" x 36" w/ (2) Mounting Brackets	\$ 706.00
1.48	Aluminum Tool Box, Frame Mounted 18" x 18" x 48" w/ (2) Mounting Brackets	\$ 845.00
1.49	Aluminum Tool Box, Frame Mounted 18" x 18" x 60" w/ (2) Mounting Brackets	\$ 963.00

Pre-Wet Options		
1.43	105 Gallon, Hydraulic Pre-Wet Tank System	\$ 4,233.00
1.44	Installation of 105 Gallon, Hydraulic Pre-Wet Tank System	\$ 778.00
1.45	(2) 105 Gallon, Hydraulic Pre-Wet Tank System	\$ 5,082.00
1.46	Installation of (2) 105 Gallon, Hydraulic Pre-Wet Tank System	\$ 1,303.00
1.47	(2) 210 Gallon, Hydraulic Pre-Wet Tank System	\$ 6,739.00
1.48	Installation of (2) 210 Gallon, Hydraulic Pre-Wet Tank System	\$ 1,303.00
1.49	(2) 400 Gallon, Hydraulic Pre-Wet Tank System	\$ 7,632.00
1.50	Installation of (2) 400 Gallon Hydraulic Pre-Wet Tank System	\$ 1,612.00
1.51	105 Gallon, 12 VDC Pre-Wet Tank System	\$ 1,880.00
1.52	Installation of 105 Gallon, 12 VDC Pre-Wet Tank System	\$ 986.00
1.53	(2) 105 Gallon, VDC Pre-Wet Tank System	\$ 2,829.00
1.54	Installation of (2) 105 Gallon, VDC Pre-Wet Tank System	\$ 1,303.00
1.55	(2) 210 Gallon, VDC Pre-Wet Tank System	\$ 4,386.00
1.56	Installation of (2) 210 Gallon, VDC Pre-Wet Tank System	\$ 1,303.00
1.57	(2) 400 Gallon, VDC Pre-Wet Tank System	\$ 5,376.00
1.58	Installation of (2) 400 Gallon VDC Pre-Wet Tank System	\$ 1,612.00
	Cost per loaded mile for pickup and or delivery of vehicle (if applicable):	\$ 4.00
	Delivery Starting Point City, State, & Zip:	
	St Cloud, MN 56304 or Fargo, ND 58078	
	Body Shop Rate	\$120.00/hr.
	Mechanic Shop Rate	\$120.00/hr.

Price quote for:	1.0 PRICE SCHEDULE DUMP BOX	
Vendor Name:	Iron Valley Equipment & Mfg. - St Cloud	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	601 Franklin Ave NE	
P.O. Box:		
City, State, Zip:	St Cloud, MN 56304	
Phone #:	320-281-3335 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Vendor Name:	Iron Valley Equipment & Mfg. - West Fargo	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	860 9th St NE Suite I	
P.O. Box:		
City, State, Zip:	West Fargo, ND 58078	
Phone #:	701-353-5226 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Item #	Information Requested	Answer
1.0	Box Make and Model	Beau-Roc Diamond RXL
	List Truck Type Box Fits	Single Axle
	Box Style	Elliptical - Stainless Steel
	Width & Length of Box	9'- 12' Long X 96" Wide
	Side Panel Description	3/16" SS201 2B
	Front Panel Description	3/16" SS201 2B
	Floor Description	3/16" Hardox 450
	Corner Post Description	Optional
	Under Structure Description	3/16" Domex 100W
	Tailgate Description	3/16" SS201 2B
	Hinge Description	Standard 3/4"
	Description of Peripheral Items (Lights, Access Steps, etc.)	FMVSS-108 Approved, Body Prop, Side Ladder, Hoist, Air Tailgate, LED Light Kit & Harness, Mounting Kit
	Is Installation included in price?	Yes ___ or No X ___
	Is Box Painted?	Yes ___ or No X ___
	Warranty Information	2 Years
	List Volume Discounts	3% - 5+ Bodies
1.1	Cost for Painting box per spec	N/A
	TOTAL PRICE:	See Below

	Description	Answer
1.2	Wiring Standoffs	Included
The Beau-Roc Diamond RXL Elliptical line features ALL SS201 2B Stainless Steel bodies with Hardox 450 Floor. Recommended for a wide range of applications from light materials hauling (sand, gravel, dirt, asphalt, etc.) to super-duty applications such as concrete, large rock & quarry work. Side features Top Rail 4" x 4" x 3/16" tubing, Board Pockets, & Ladder; Rear & Tailgate feature Double-Acting D-A banjos inst, 84" chains & shackles, air tailgate latch. Cylinders are factory installed to bodies at Mfg. Facility.		
	Model RXL Single Axle Elliptical Stainless Steel	
1.3	Length 9'; Hoist G4-80-4.25-3	\$ 24,087.00
1.4	Length 9'6"; Hoist G4-90-4.25-3	\$ 24,411.00
1.5	Length 10'; Hoist G4-90-4.25-3	\$ 24,636.00
1.6	Length 10'6"; Hoist G4-90-4.25-3	\$ 24,863.00
1.7	Length 11'; Hoist G4-100-4.25-3	\$ 25,113.00
1.8	Length 11'6"; Hoist G4-100-4.25-3	\$ 25,338.00
1.9	Length 12'; Hoist G4-110-4.25-3	\$ 25,565.00
	Options:	
1.10	Installation of Single Axle RXL Elliptical Stainless Steel Bodies	\$ 2,485.00
1.11	Undercoating of Body	\$ 1,313.00
1.12	LED Lighting	\$ 375.00
1.13	Box Vibrator	\$ 2,344.00
1.14	12" Cab shield	\$ 638.00
1.15	10' Hook lift A-Frame 54" or 62" Hook Height Without Rollers	\$ 5,480.00
1.16	10' Hook lift A-Frame 54" or 62" Hook Height With Rollers	\$ 5,789.00
1.17	11' Hook lift A-Frame 54" or 62" Hook Height Without Rollers	\$ 6,139.00
1.18	11' Hook lift A-Frame 54" or 62" Hook Height With Rollers	\$ 6,654.00
1.19	16' Hook lift A-Frame 54" or 62" Hook Height Without Rollers	\$ 7,292.00
1.20	16' Hook lift A-Frame 54" or 62" Hook Height With Rollers	\$ 7,807.00
1.21	105 Gallon Electric 3 GPM Pre-Wet Tailgate Mount System	\$ 3,492.00
1.22	105 Gallon Hydraulic 4.5 GPM Pre-Wet Tailgate Mount System	\$ 5,577.00
1.23	Installation of Pre-Wet System	\$ 1,185.00
1.24	BPC Poly Fenders for Single Axle w/Mounting Kit	\$ 1,009.00
1.25	Pull Tarp - Up to 12'	\$ 1,427.00
1.26	Pull Tarp - Up to 16'	\$ 1,780.00
1.27	Electric Tarp w/Tension Bow	\$ 3,646.00
1.28	Warning Light Package: (12) Surface Mount LED Warning Lights, Class 1 Rated, 5 Year	\$ 1,911.00
1.29	Warning Light Package: (6) Surface Mount LED Warning Lights: Class 1 Rated, 5 Year	\$ 1,007.00
1.30	Two LED Mirror Mount Warning Lights, Class 1 Rated	\$ 845.00
1.31	Additional Set 6 1/2" Oval Cut-Out in Rear of Body: 1 Set of LED Lights	\$ 541.00
1.32	LED Flood Light, 12/24-5" Square	\$ 195.00
1.33	LED Flood Light, 12/24-6" Square	\$ 202.00
1.34	LED Class 1 Light Bar, 5 Year Warranty	\$ 521.00
1.35	Night Vision Camera w/LED Screen, Color, Heated	\$ 1,059.00
1.36	Additional Camera	\$ 391.00
1.37	Back-Up Alarm, Installed	\$ 499.00
1.38	Aluminum Tool Box, Frame Mounted 18" x 18" x 18" w/ (2) Mounting Brackets	\$ 561.00
1.39	Aluminum Tool Box, Frame Mounted 18" x 18" x 24" w/ (2) Mounting Brackets	\$ 613.00
1.40	Aluminum Tool Box, Frame Mounted 18" x 18" x 36" w/ (2) Mounting Brackets	\$ 706.00
1.41	Aluminum Tool Box, Frame Mounted 18" x 18" x 48" w/ (2) Mounting Brackets	\$ 845.00
1.42	Aluminum Tool Box, Frame Mounted 18" x 18" x 60" w/ (2) Mounting Brackets	\$ 963.00

Pre-Wet Options		
1.43	105 Gallon, Hydraulic Pre-Wet Tank System	\$ 4,233.00
1.44	Installation of 105 Gallon, Hydraulic Pre-Wet Tank System	\$ 778.00
1.45	(2) 105 Gallon, Hydraulic Pre-Wet Tank System	\$ 5,082.00
1.46	Installation of (2) 105 Gallon, Hydraulic Pre-Wet Tank System	\$ 1,303.00
1.47	(2) 210 Gallon, Hydraulic Pre-Wet Tank System	\$ 6,739.00
1.48	Installation of (2) 210 Gallon, Hydraulic Pre-Wet Tank System	\$ 1,303.00
1.49	(2) 400 Gallon, Hydraulic Pre-Wet Tank System	\$ 7,632.00
1.50	Installation of (2) 400 Gallon Hydraulic Pre-Wet Tank System	\$ 1,612.00
1.51	105 Gallon, 12 VDC Pre-Wet Tank System	\$ 1,880.00
1.52	Installation of 105 Gallon, 12 VDC Pre-Wet Tank System	\$ 986.00
1.53	(2) 105 Gallon, VDC Pre-Wet Tank System	\$ 2,827.00
1.54	Installation of (2) 105 Gallon, VDC Pre-Wet Tank System	\$ 1,303.00
1.55	(2) 210 Gallon, VDC Pre-Wet Tank System	\$ 4,386.00
1.56	Installation of (2) 210 Gallon, VDC Pre-Wet Tank System	\$ 1,303.00
1.57	(2) 400 Gallon, VDC Pre-Wet Tank System	\$ 5,376.00
1.58	Installation of (2) 400 Gallon VDC Pre-Wet Tank System	\$ 1,612.00
	Cost per loaded mile for pickup and or delivery of vehicle (if applicable):	\$ 4.00
	Delivery Starting Point City, State, & Zip:	
	St Cloud, MN 56304 or Fargo, ND 58078	
	Body Shop Rate	\$120.00/hr.
	Mechanic Shop Rate	\$120.00/hr.

Price quote for:	1.0 PRICE SCHEDULE DUMP BOX	
Vendor Name:	Iron Valley Equipment & Mfg. - St Cloud	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	601 Franklin Ave NE	
P.O. Box:		
City, State, Zip:	St Cloud, MN 56304	
Phone #:	320-281-3335 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Vendor Name:	Iron Valley Equipment & Mfg. - West Fargo	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	860 9th St NE Suite I	
P.O. Box:		
City, State, Zip:	West Fargo, ND 58078	
Phone #:	701-353-5226 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Item #	Information Requested	Answer
1.0	Box Make and Model	Beau-Roc Diamond RXL
	List Truck Type Box Fits	Tandem Axle
	Box Style	Elliptical - Steel
	Width & Length of Box	14' - 15'6" Long X 96" Wide
	Side Panel Description	Hardox 450
	Front Panel Description	Hardox 450
	Floor Description	3/16" Hardox 450
	Corner Post Description	None
	Under Structure Description	1/4" 44-W
	Tailgate Description	42" Hardox 450
	Hinge Description	Standard 3/4"
	Description of Peripheral Items (Lights, Access Steps, etc.)	FMVSS-108 Approved, Body Prop, Side Ladder, Hoist, Air Tailgate, LED Light Kit & Harness, Mounting
	Is Installation included in price?	Yes ___ or No <u>X</u>
	Is Box Painted?	Yes ___ or No <u>X</u>
	Warranty Information	2 Years
	List Volume Discounts	3 - 5+ Bodies
1.1	Cost for Painting box per spec	See Options Below
	TOTAL PRICE:	See Below

	Description	Answer
1.2	Wiring Standoffs	Included
The Beau-Roc Diamond RXL Elliptical line features ALL Hardox bodies. Recommended for a wide range of applications from light materials hauling (sand, gravel, dirt, asphalt, etc.) to super-duty applications such as concrete, large rock & quarry work. Side features Top Rail 4" x 4" x 3/16" tubing, Board Pockets, & Ladder; Rear & Tailgate feature Double-Acting D-A banjos inst, 84" chains & shackles, air tailgate latch. Cylinders are factory		
	Model RXL Tandem Elliptical Steel	
1.3	14'; Hoist G3130-5-3	\$ 18,839.00
1.4	14'6"; Hoist G3-130-5-3	\$ 19,061.00
1.5	15'; Hoist G3-140-5-3	\$ 19,389.00
1.6	15'6"; Hoist G3-140-5-3	\$ 19,612.00
	Options:	
1.7	Installation of Tandem Axle RXL Elliptical Steel Bodies	\$ 2,766.00
1.8	Painting of 14' Body - Non Metallic	\$ 3,657.00
1.9	Painting of 14'6" Body - Non Metallic	\$ 3,708.00
1.10	Painting of 15' Body - Non Metallic	\$ 3,723.00
1.11	Painting of 15'6" Body - Non Metallic	\$ 3,739.00
1.12	Undercoating of Body	\$ 1,700.00
1.13	LED Lighting	\$ 375.00
1.14	Box Vibrator	\$ 2,756.00
1.15	12" Cab shield	\$ 387.00
1.16	16' Hook lift A-Frame 54" or 62" Hook Height Without Rollers	\$ 7,292.00
1.17	16' Hook lift A-Frame 54" or 62" Hook Height With Rollers	\$ 7,807.00
1.18	105 Gallon Electric 3 GPM Pre-Wet Tailgate Mount System	\$ 3,492.00
1.19	105 Gallon Hydraulic 4.5 GPM Pre-Wet Tailgate Mount System	\$ 5,577.00
1.20	Installation of Pre-Wet System	\$ 1,185.00
1.21	BPC Poly Fenders for Tandem Axle w/Mounting Kit	\$ 1,465.00
1.22	Pull Tarp - Up to 16'	\$ 1,780.00
1.23	Electric Tarp w/Tension Bow	\$ 3,646.00
1.24	Warning Light Package: (12) Surface Mount LED Warning Lights, Class 1 Rated, 5 Year Warranty	\$ 1,911.00
1.25	Warning Light Package: (6) Surface Mount LED Warning Lights: Class 1 Rated, 5 Year Warranty	\$ 1,007.00
1.26	Two LED Mirror Mount Warning Lights, Class 1 Rated	\$ 845.00
1.27	Additional Set 6 1/2" Oval Cut-Out in Rear of Body: 1 Set of LED Lights	\$ 541.00
1.28	LED Flood Light, 12/24-5" Square	\$ 195.00
1.29	LED Flood Light, 12/24-6" Square	\$ 202.00
1.30	LED Class 1 Light Bar, 5 Year Warranty	\$ 541.00
1.31	Night Vision Camera w/LED Screen, Color, Heated	\$ 1,059.00
1.32	Additional Camera	\$ 391.00
1.33	Back-Up Alarm, Installed	\$ 499.00
1.34	Aluminum Tool Box, Frame Mounted 18" x 18" x 18" w/ (2) Mounting Brackets	\$ 561.00
1.35	Aluminum Tool Box, Frame Mounted 18" x 18" x 24" w/ (2) Mounting Brackets	\$ 613.00
1.36	Aluminum Tool Box, Frame Mounted 18" x 18" x 36" w/ (2) Mounting Brackets	\$ 706.00
1.37	Aluminum Tool Box, Frame Mounted 18" x 18" x 48" w/ (2) Mounting Brackets	\$ 845.00
1.38	Aluminum Tool Box, Frame Mounted 18" x 18" x 60" w/ (2) Mounting Brackets	\$ 963.00

Pre-Wet Options		
1.39	105 Gallon, Hydraulic Pre-Wet Tank System	\$ 4,233.00
1.40	Installation of 105 Gallon, Hydraulic Pre-Wet Tank System	\$ 778.00
1.41	(2) 105 Gallon, Hydraulic Pre-Wet Tank System	\$ 5,082.00
1.42	Installation of (2) 105 Gallon, Hydraulic Pre-Wet Tank System	\$ 1,303.00
1.43	(2) 210 Gallon, Hydraulic Pre-Wet Tank System	\$ 6,739.00
1.44	Installation of (2) 210 Gallon, Hydraulic Pre-Wet Tank System	\$ 1,303.00
1.45	(2) 400 Gallon, Hydraulic Pre-Wet Tank System	\$ 7,632.00
1.46	Installation of (2) 400 Gallon Hydraulic Pre-Wet Tank System	\$ 1,612.00
1.47	105 Gallon, 12 VDC Pre-Wet Tank System	\$ 1,880.00
1.48	Installation of 105 Gallon, 12 VDC Pre-Wet Tank System	\$ 986.00
1.49	(2) 105 Gallon, VDC Pre-Wet Tank System	\$ 2,829.00
1.50	Installation of (2) 105 Gallon, VDC Pre-Wet Tank System	\$ 1,303.00
1.51	(2) 210 Gallon, VDC Pre-Wet Tank System	\$ 4,386.00
1.52	Installation of (2) 210 Gallon, VDC Pre-Wet Tank System	\$ 1,303.00
1.53	(2) 400 Gallon, VDC Pre-Wet Tank System	\$ 5,376.00
1.54	Installation of (2) 400 Gallon VDC Pre-Wet Tank System	\$ 1,612.00
	Cost per loaded mile for pickup and or delivery of vehicle (if applicable):	\$ 4.00
	Delivery Starting Point City, State, & Zip:	
	St Cloud, MN 56304 or Fargo, ND 58078	
	Body Shop Rate	\$120.00/hr.
	Mechanic Shop Rate	\$120.00/hr.

Price quote for:	1.0 PRICE SCHEDULE DUMP BOX	
Vendor Name:	Iron Valley Equipment & Mfg. - St Cloud	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	601 Franklin Ave NE	
P.O. Box:		
City, State, Zip:	St Cloud, MN 56304	
Phone #:	320-281-3335 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Vendor Name:	Iron Valley Equipment & Mfg. - West Fargo	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	860 9th St NE Suite I	
P.O. Box:		
City, State, Zip:	West Fargo, ND 58078	
Phone #:	701-353-5226 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Item #	Information Requested	Answer
1.0	Box Make and Model	Beau-Roc Diamond RXL
	List Truck Type Box Fits	Tandem Axle
	Box Style	Elliptical - Stainless Steel
	Width & Length of Box	14' - 15'6" Long X 96" Wide
	Side Panel Description	3/16" SS201 2B
	Front Panel Description	3/16" SS201 2B
	Floor Description	3/16" Hardox 450
	Corner Post Description	None
	Under Structure Description	3/16" Domex 100W
	Tailgate Description	3/16" SS201 2B
	Hinge Description	Standard 3/4"
	Description of Peripheral Items (Lights, Access Steps, etc.)	FMVSS-108 Approved, Body Prop, Side Ladder, Hoist, Air Tailgate, LED Light Kit & Harness, Mounting Kit
	Is Installation included in price?	Yes or No X
	Is Box Painted?	Yes or No X
	Warranty Information	2 Years
	List Volume Discounts	3% - 5+ Bodies
1.1	Cost for Painting box per spec	N/A
	TOTAL PRICE:	See Below

	Description	Answer
1.2	Wiring Standoffs	Included
<p>The Beau-Roc Diamond RXL Elliptical line features ALL SS201 2B Stainless Steel bodies with 3/16" Hardox Floor. Recommended for a wide range of applications from light materials hauling (sand, gravel, dirt, asphalt, etc.) to super-duty applications such as concrete, large rock & quarry work. Side features Top Rail 4" x 4" x 3/16" tubing, Board Pockets, & Ladder; Rear & Tailgate feature Double-Acting D-A banjos inst, 84" chains & shackles, air tailgate latch. Cylinders are factory installed to bodies at Mfg. Facility.</p>		
	Model RXL Tandem Elliptical Stainless	
1.3	14'; Hoist G4-130-5-3	\$ 27,622.00
1.4	14'6"; Hoist G4-130-5-3	\$ 27,850.00
1.5	15'; Hoist G4-140-5-3	\$ 28,186.00
1.6	15'6"; Hoist G4-140-5-3	\$ 28,416.00
	Options:	
1.7	Installation of Tandem Axle RXL Elliptical Stainless Steel Bodies	\$ 3,985.00
1.8	Undercoating of Body	\$ 1,700.00
1.9	LED Lighting	\$ 375.00
1.10	Box Vibrator	\$ 2,756.00
1.11	12" Cab shield	\$ 1,256.00
1.12	16' Hook lift A-Frame 54" or 62" Hook Height Without Rollers	\$ 7,292.00
1.13	16' Hook lift A-Frame 54" or 62" Hook Height With Rollers	\$ 7,807.00
1.14	105 Gallon Electric 3 GPM Pre-Wet Tailgate Mount System	\$ 3,492.00
1.15	105 Gallon Hydraulic 4.5 GPM Pre-Wet Tailgate Mount System	\$ 5,577.00
1.16	Installation of Pre-Wet System	\$ 1,185.00
1.17	BPC Poly Fenders for Tandem Axle w/Mounting Kit	\$ 1,465.00
1.18	Pull Tarp - Up to 16'	\$ 1,780.00
1.19	Electric Tarp w/Tension Bow	\$ 3,646.00
1.20	Warning Light Package: (12) Surface Mount LED Warning Lights, Class 1 Rated, 5 Year	\$ 1,911.00
1.21	Warning Light Package: (6) Surface Mount LED Warning Lights: Class 1 Rated, 5 Year	\$ 1,007.00
1.22	Two LED Mirror Mount Warning Lights, Class 1 Rated	\$ 845.00
1.23	Additional Set 6 1/2" Oval Cut-Out in Rear of Body: 1 Set of LED Lights	\$ 541.00
1.24	LED Flood Light, 12/24-5" Square	\$ 195.00
1.25	LED Flood Light, 12/24-6" Square	\$ 202.00
1.26	LED Class 1 Light Bar, 5 Year Warranty	\$ 541.00
1.27	Night Vision Camera w/LED Screen, Color, Heated	\$ 853.00
1.28	Additional Camera	\$ 288.00
1.29	Back-Up Alarm, Installed	\$ 499.00
1.30	Aluminum Tool Box, Frame Mounted 18" x 18" x 18" w/ (2) Mounting Brackets	\$ 561.00
1.31	Aluminum Tool Box, Frame Mounted 18" x 18" x 24" w/ (2) Mounting Brackets	\$ 613.00
1.32	Aluminum Tool Box, Frame Mounted 18" x 18" x 36" w/ (2) Mounting Brackets	\$ 706.00
1.33	Aluminum Tool Box, Frame Mounted 18" x 18" x 48" w/ (2) Mounting Brackets	\$ 845.00
1.34	Aluminum Tool Box, Frame Mounted 18" x 18" x 60" w/ (2) Mounting Brackets	\$ 963.00

Pre-Wet Options		
1.35	105 Gallon, Hydraulic Pre-Wet Tank System	\$ 4,110.00
1.36	Installation of 105 Gallon, Hydraulic Pre-Wet Tank System	\$ 778.00
1.37	(2) 105 Gallon, Hydraulic Pre-Wet Tank System	\$ 5,082.00
1.38	Installation of (2) 105 Gallon, Hydraulic Pre-Wet Tank System	\$ 1,303.00
1.39	(2) 210 Gallon, Hydraulic Pre-Wet Tank System	\$ 6,739.00
1.40	Installation of (2) 210 Gallon, Hydraulic Pre-Wet Tank System	\$ 1,303.00
1.41	(2) 400 Gallon, Hydraulic Pre-Wet Tank System	\$ 7,632.00
1.42	Installation of (2) 400 Gallon Hydraulic Pre-Wet Tank System	\$ 1,612.00
1.43	105 Gallon, 12 VDC Pre-Wet Tank System	\$ 1,880.00
1.44	Installation of 105 Gallon, 12 VDC Pre-Wet Tank System	\$ 986.00
1.45	(2) 105 Gallon, VDC Pre-Wet Tank System	\$ 2,829.00
1.46	Installation of (2) 105 Gallon, VDC Pre-Wet Tank System	\$ 1,303.00
1.47	(2) 210 Gallon, VDC Pre-Wet Tank System	\$ 4,386.00
1.48	Installation of (2) 210 Gallon, VDC Pre-Wet Tank System	\$ 1,303.00
1.49	(2) 400 Gallon, VDC Pre-Wet Tank System	\$ 5,376.00
1.50	Installation of (2) 400 Gallon VDC Pre-Wet Tank System	\$ 1,612.00
	Cost per loaded mile for pickup and or delivery of vehicle (if applicable):	\$ 4.00
	Delivery Starting Point City, State, & Zip:	
	St Cloud, MN 56304 or Fargo, ND 58078	
	Body Shop Rate	\$120.00/hr.
	Mechanic Shop Rate	\$120.00/hr.

Price quote for:	1.0 PRICE SCHEDULE DUMP BOX	
Vendor Name:	Iron Valley Equipment & Mfg. - St Cloud	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	601 Franklin Ave NE	
P.O. Box:		
City, State, Zip:	St Cloud, MN 56304	
Phone #:	320-281-3335 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Vendor Name:	Iron Valley Equipment & Mfg. - West Fargo	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	860 9th St NE Suite I	
P.O. Box:		
City, State, Zip:	West Fargo, ND 58078	
Phone #:	701-353-5226 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Item #	Information Requested	Answer
1.0	Box Make and Model	Beau-Roc Diamond RXL
	List Truck Type Box Fits	Tri Axle - Quad Axle
	Box Style	Elliptical - Steel
	Width & Length of Box	16' - 18' Long X 96" Wide
	Side Panel Description	Hardox 450
	Front Panel Description	Hardox 450
	Floor Description	3/16" Hardox 450
	Corner Post Description	None
	Under Structure Description	1/4" 44-W
	Tailgate Description	42" Hardox 450
	Hinge Description	Standard 3/4"
	Description of Peripheral Items (Lights, Access Steps, etc.)	FMVSS-108 Approved, Body Prop, Side Ladder, Hoist, Air Tailgate, LED Light Kit & Harness, Mounting Kit
	Is Installation included in price?	Yes or No <u>X</u>
	Is Box Painted?	Yes or No <u>X</u>
	Warranty Information	2 Years
	List Volume Discounts	3% - 5+ Bodies
1.1	Cost for Painting box per spec	See Options Below
	TOTAL PRICE:	See Below

	Description	Answer
1.2	Wiring Standoffs	Included
The Beau-Roc Diamond RXL Elliptical line features ALL Hardox bodies. Recommended for a wide range of applications from light materials hauling (sand, gravel, dirt, asphalt, etc.) to super-duty applications such as concrete, large rock & quarry work. Side features Top Rail 4" x 4" x 3/16" tubing, Board Pockets, & Ladder; Rear & Tailgate feature Double-Acting D-A banjos inst, 84" chains & shackles, air tailgate latch. Cylinders are factory installed to bodies at Mfg. Facility.		
	Model RXL Tri - Quad Axle Elliptical Steel	
1.3	Length 16'; Sill Height 8"; Hoist G3-150-5.7-4	\$ 28,524.00
1.4	Length 16'6"; Sill Height 8"; Hoist G3-150-5.7-4	\$ 28,725.00
1.5	Length 17'; Sill Height 8"; Hoist G3-150-5.7-4	\$ 28,707.00
1.6	Length 17'6"; Sill Height 8"; Hoist G3-160-5.7-4	\$ 29,702.00
1.7	Length 18'; Sill Height 10"; Hoist G3-160-5.7-4	\$ 30,533.00
	Add for 1/4" Hardox450 Floor	
1.8	Length 16'	\$ 852.00
1.9	Length 16'6"	\$ 1,005.00
1.10	Length 17'	\$ 1,159.00
1.11	Length 17'6"	\$ 1,444.00
1.12	Length 18'	\$ 1,718.00
	Options:	
1.13	Installation of Tri - Quad Axle RXL Elliptical Steel Bodies	\$ 3,985.00
1.14	Painting of 16' Body - Non Metallic	\$ 3,760.00
1.15	Painting of 16'5" Body - Non Metallic	\$ 3,940.00
1.16	Painting of 17' Body - Non Metallic	\$ 4,002.00
1.17	Painting of 17'6" Body - Non Metallic	\$ 4,063.00
1.18	Painting of 18' Body - Non Metallic	\$ 4,120.00
1.19	Undercoating of Body	\$ 2,009.00
1.20	LED Lighting	\$ 375.00
1.21	Box Vibrator	\$ 3,570.00
1.22	12" Cab shield	\$ 646.00
1.23	Internal Air High Lift	\$ 3,383.00
1.24	16' Hook lift A-Frame 54" or 62" Hook Height Without Rollers	\$ 7,292.00
1.25	16' Hook lift A-Frame 54" or 62" Hook Height With Rollers	\$ 7,807.00
1.26	105 Gallon Electric 3 GPM Pre-Wet Tailgate Mount System	\$ 3,492.00
1.27	105 Gallon Hydraulic 4.5 GPM Pre-Wet Tailgate Mount System	\$ 5,577.00
1.28	Installation of Pre-Wet System	\$ 1,185.00
1.29	Pull Tarp - Up to 16'	\$ 1,780.00
1.30	Electric Tarp w/Tension Bow	\$ 3,646.00
1.31	Warning Light Package: (12) Surface Mount LED Warning Lights, Class 1 Rated, 5 Year	\$ 1,911.00
1.32	Warning Light Package: (6) Surface Mount LED Warning Lights: Class 1 Rated, 5 Year	\$ 1,007.00
1.33	Two LED Mirror Mount Warning Lights, Class 1 Rated	\$ 845.00
1.34	Additional Set 6 1/2" Oval Cut-Out in Rear of Body: 1 Set of LED Lights	\$ 541.00
1.35	LED Flood Light, 12/24-5" Square	\$ 195.00
1.36	LED Flood Light, 12/24-6" Square	\$ 202.00
1.37	LED Class 1 Light Bar, 5 Year Warranty	\$ 541.00
1.38	Night Vision Camera w/LED Screen, Color, Heated	\$ 1,059.00
1.39	Additional Camera	\$ 391.00
1.40	Back-Up Alarm, Installed	\$ 499.00
1.41	Aluminum Tool Box, Frame Mounted 18" x 18" x 18" w/ (2) Mounting Brackets	\$ 561.00
1.42	Aluminum Tool Box, Frame Mounted 18" x 18" x 24" w/ (2) Mounting Brackets	\$ 613.00
1.43	Aluminum Tool Box, Frame Mounted 18" x 18" x 36" w/ (2) Mounting Brackets	\$ 706.00
1.44	Aluminum Tool Box, Frame Mounted 18" x 18" x 48" w/ (2) Mounting Brackets	\$ 845.00
1.45	Aluminum Tool Box, Frame Mounted 18" x 18" x 60" w/ (2) Mounting Brackets	\$ 963.00

Pre-Wet Options		
1.46	105 Gallon, Hydraulic Pre-Wet Tank System	\$ 4,233.00
1.47	Installation of 105 Gallon, Hydraulic Pre-Wet Tank System	\$ 778.00
1.48	(2) 105 Gallon, Hydraulic Pre-Wet Tank System	\$ 5,082.00
1.49	Installation of (2) 105 Gallon, Hydraulic Pre-Wet Tank System	\$ 1,303.00
1.50	(2) 210 Gallon, Hydraulic Pre-Wet Tank System	\$ 6,739.00
1.51	Installation of (2) 210 Gallon, Hydraulic Pre-Wet Tank System	\$ 1,303.00
1.52	(2) 400 Gallon, Hydraulic Pre-Wet Tank System	\$ 7,632.00
1.53	Installation of (2) 400 Gallon Hydraulic Pre-Wet Tank System	\$ 1,612.00
1.54	105 Gallon, 12 VDC Pre-Wet Tank System	\$ 1,880.00
1.55	Installation of 105 Gallon, 12 VDC Pre-Wet Tank System	\$ 986.00
1.56	(2) 105 Gallon, VDC Pre-Wet Tank System	\$ 2,829.00
1.57	Installation of (2) 105 Gallon, VDC Pre-Wet Tank System	\$ 1,303.00
1.58	(2) 210 Gallon, VDC Pre-Wet Tank System	\$ 4,386.00
1.59	Installation of (2) 210 Gallon, VDC Pre-Wet Tank System	\$ 1,303.00
1.60	(2) 400 Gallon, VDC Pre-Wet Tank System	\$ 5,376.00
1.61	Installation of (2) 400 Gallon VDC Pre-Wet Tank System	\$ 1,612.00
	Cost per loaded mile for pickup and or delivery of vehicle (if applicable):	\$ 4.00
	Delivery Starting Point City, State, & Zip:	
	St Cloud, MN 56304 or Fargo, ND 58078	
	Body Shop Rate	\$120.00/hr.
	Mechanic Shop Rate	\$120.00/hr.

Price quote for:	1.0 PRICE SCHEDULE DUMP BOX	
Vendor Name:	Iron Valley Equipment & Mfg. - St Cloud	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	601 Franklin Ave NE	
P.O. Box:		
City, State, Zip:	St Cloud, MN 56304	
Phone #:	320-281-3335 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Vendor Name:	Iron Valley Equipment & Mfg. - West Fargo	
Contact Person:	Adele Perkins or Patrick Iwan	
Street Address:	860 9th St NE Suite I	
P.O. Box:		
City, State, Zip:	West Fargo, ND 58078	
Phone #:	701-353-5226 or 651-829-4547	
Toll Free #:		
Fax #:		
Email Address:	Adele@IronValleyEquipment.com or Patrick@IronValleyEquipment.com	
Item #	Information Requested	Answer
1.0	Box Make and Model	Beau-Roc Diamond RXL
	List Truck Type Box Fits	Tri - Quad Axle
	Box Style	Elliptical - Stainless Steel
	Width & Length of Box	16' - 18' Long X 96" Wide
	Side Panel Description	3/16" SS201 2B
	Front Panel Description	3/16" SS201 2B
	Floor Description	3/16" Hardox 450
	Corner Post Description	None
	Under Structure Description	3/16" Domex 100W
	Tailgate Description	3/16" SS201 2B
	Hinge Description	Standard 3/4"
	Description of Peripheral Items (Lights, Access Steps, etc.)	FMVSS-108 Approved, Body Prop, Side Ladder, Hoist, Air Tailgate, LED Light Kit & Harness, Mounting Kit
	Is Installation included in price?	Yes <input type="checkbox"/> or No <input checked="" type="checkbox"/>
	Is Box Painted?	Yes <input type="checkbox"/> or No <input checked="" type="checkbox"/>
	Warranty Information	2 Years
	List Volume Discounts	3% - 5+ Bodies
1.1	Cost for Painting box per spec	N/A
TOTAL PRICE:		See Below

	Description	Answer
1.2	Wiring Standoffs	Included
The Beau-Roc Diamond RXL Elliptical line features ALL SS201 2B Stainless Steel bodies with 3/16" Hardox Floor. Recommended for a wide range of applications from light materials hauling (sand, gravel, dirt, asphalt, etc.) to super-duty applications such as concrete, large rock & quarry work. Side features Top Rail 4" x 4" x 3/16" tubing, Board Pockets, & Ladder; Rear & Tailgate feature Double-Acting D-A banjos inst, 84" chains & shackles, air tailgate latch. Cylinders are factory installed to bodies at Mfg. Facility.		
Model RXL Tri - Quad Axle Elliptical Stainless		
1.3	Length 16'; Sill Height 8"; Hoist G4-135-5.7-4	\$ 34,878.00
1.4	Length 16'6"; Sill Height 8"; Hoist G4-150-5.7-4	\$ 36,048.00
1.5	Length 17'; Sill Height 8"; Hoist G4-150-5.7-4	\$ 36,328.00
1.6	Length 17'6"; Sill Height 8"; Hoist G4-160-5.7-4	\$ 36,617.00
1.7	Length 18'; Sill Height 10"; Hoist G4-160-5.7-4	\$ 37,074.00
Add for 1/4" Hardox450 Floor		
1.10	Length 16'	\$ 852.00
1.11	Length 16'6"	\$ 1,005.00
1.12	Length 17'	\$ 1,159.00
1.13	Length 17'6"	\$ 1,444.00
1.14	Length 18'	\$ 1,718.00
Options:		
1.17	Installation of Tri - Quad Axle RXL Elliptical Stainless Steel Bodies	\$ 3,985.00
1.18	Undercoating of Body	\$ 2,009.00
1.19	LED Lighting	\$ 375.00
1.20	Box Vibrator	\$ 3,261.00
1.21	12" Cab shield	\$ 691.00
1.22	Internal Air High Lift	\$ 3,383.00
1.23	16' Hook lift A-Frame 54" or 62" Hook Height Without Rollers	\$ 7,292.00
1.24	16' Hook lift A-Frame 54" or 62" Hook Height With Rollers	\$ 7,807.00
1.25	105 Gallon Electric 3 GPM Pre-Wet Tailgate Mount System	\$ 3,492.00
1.26	105 Gallon Hydraulic 4.5 GPM Pre-Wet Tailgate Mount System	\$ 5,577.00
1.27	Installation of Pre-Wet System	\$ 1,185.00
1.28	Pull Tarp - Up to 16'	\$ 1,780.00
1.29	Electric Tarp w/Tension Bow	\$ 3,646.00
1.30	Warning Light Package: (12) Surface Mount LED Warning Lights, Class 1 Rated, 5 Year	\$ 1,911.00
1.31	Warning Light Package: (6) Surface Mount LED Warning Lights: Class 1 Rated, 5 Year	\$ 1,007.00
1.32	Two LED Mirror Mount Warning Lights, Class 1 Rated	\$ 845.00
1.33	Additional Set 6 1/2" Oval Cut-Out in Rear of Body: 1 Set of LED Lights	\$ 541.00
1.34	LED Flood Light, 12/24-5" Square	\$ 195.00
1.35	LED Flood Light, 12/24-6" Square	\$ 202.00
1.36	LED Class 1 Light Bar, 5 Year Warranty	\$ 541.00
1.37	Night Vision Camera w/LED Screen, Color, Heated	\$ 1,059.00
1.38	Additional Camera	\$ 391.00
1.39	Back-Up Alarm, Installed	\$ 499.00
1.40	Aluminum Tool Box, Frame Mounted 18" x 18" x 18" w/ (2) Mounting Brackets	\$ 561.00
1.41	Aluminum Tool Box, Frame Mounted 18" x 18" x 24" w/ (2) Mounting Brackets	\$ 613.00
1.42	Aluminum Tool Box, Frame Mounted 18" x 18" x 36" w/ (2) Mounting Brackets	\$ 706.00
1.43	Aluminum Tool Box, Frame Mounted 18" x 18" x 48" w/ (2) Mounting Brackets	\$ 845.00
1.44	Aluminum Tool Box, Frame Mounted 18" x 18" x 60" w/ (2) Mounting Brackets	\$ 963.00

Pre-Wet Options		
1.45	105 Gallon, Hydraulic Pre-Wet Tank System	\$ 4,233.00
1.46	Installation of 105 Gallon, Hydraulic Pre-Wet Tank System	\$ 778.00
1.47	(2) 105 Gallon, Hydraulic Pre-Wet Tank System	\$ 5,082.00
1.48	Installation of (2) 105 Gallon, Hydraulic Pre-Wet Tank System	\$ 1,303.00
1.49	(2) 210 Gallon, Hydraulic Pre-Wet Tank System	\$ 6,739.00
1.50	Installation of (2) 210 Gallon, Hydraulic Pre-Wet Tank System	\$ 1,303.00
1.51	(2) 400 Gallon, Hydraulic Pre-Wet Tank System	\$ 7,632.00
1.52	Installation of (2) 400 Gallon Hydraulic Pre-Wet Tank System	\$ 1,612.00
1.53	105 Gallon, 12 VDC Pre-Wet Tank System	\$ 1,880.00
1.54	Installation of 105 Gallon, 12 VDC Pre-Wet Tank System	\$ 986.00
1.55	(2) 105 Gallon, VDC Pre-Wet Tank System	\$ 2,829.00
1.56	Installation of (2) 105 Gallon, VDC Pre-Wet Tank System	\$ 1,303.00
1.57	(2) 210 Gallon, VDC Pre-Wet Tank System	\$ 4,386.00
1.58	Installation of (2) 210 Gallon, VDC Pre-Wet Tank System	\$ 1,303.00
1.59	(2) 400 Gallon, VDC Pre-Wet Tank System	\$ 5,376.00
1.60	Installation of (2) 400 Gallon VDC Pre-Wet Tank System	\$ 1,612.00
	Cost per loaded mile for pickup and or delivery of vehicle (if applicable):	\$ 4.00
	Delivery Starting Point City, State, & Zip:	
	St Cloud, MN 56304 or Fargo, ND 58078	
	Body Shop Rate	\$120.00/hr.
	Mechanic Shop Rate	\$120.00/hr.