


RECTANGULAR PLATES

RADIAL PLATES



TYPICAL RADIAL TRUNCATED DOME PLATES			
RADIUS (FEET)	LONG CHORD WIDTH (INCHES)	SQ. FT. PER PLATE	PLATES REQUIRED FOR 90 DEGREE TURN
⑦			
10	23-1/2	3.53	8
15	18-13/16	2.93	15
15	23-1/2	3.67	12
20	18-13/16	3.00	20
20	18-7/8	2.98	20
25	20-1/2	3.28	23
25	23-9/16	3.77	20
30	22-5/8	3.65	25
35	22	3.56	30

NOTES:

DETECTABLE WARNING SURFACES SHALL FOLLOW THE PUBLIC RIGHTS-OF-WAY ACCESSIBILITY GUIDELINES (PROWAG).

DETECTABLE WARNINGS CONSIST OF TRUNCATED DOMES ALIGNED IN A SQUARE OR RADIAL GRID PATTERN.

DETECTABLE WARNINGS ARE REQUIRED:

- WHERE RAMP, LANDINGS, OR BLENDED TRANSITIONS PROVIDE A FLUSH PEDESTRIAN CONNECTION TO THE ROADWAY.
- WHERE PEDESTRIAN ACCESS ROUTES CROSS COMMERCIAL DRIVEWAYS THAT ARE PROVIDED WITH TRAFFIC CONTROL DEVICES OR OTHERWISE PERMITTED TO OPERATE LIKE A PUBLIC ROADWAY.
- AT PEDESTRIAN RAILWAY CROSSINGS.
- ON RAIL PLATFORMS WHERE BOARDING EDGES ARE NOT PROTECTED.

DETECTABLE WARNINGS SHALL EXTEND:

- A MINIMUM OF 24" IN THE DIRECTION OF TRAVEL.
- THE FULL WIDTH OF THE RAMP, LANDING, OR BLENDED TRANSITION, WITHIN 3" OF FULL WIDTH ON EITHER END.
- THE FULL LENGTH OF THE PUBLIC USE AREA OF A RAIL PLATFORM.

DETECTABLE WARNING SURFACES SHALL CONTRAST VISUALLY WITH ADJACENT GUTTER, ROADWAY, OR WALKWAY, EITHER A LIGHT-ON-DARK OR DARK-ON-LIGHT. CONTRAST MAY BE PROVIDED ON THE FULL RAMP SURFACE, EXCLUDING THE FLARED SIDES.

FOR MN/DOT PROJECTS, SEE MN/DOT'S APPROVED/QUALIFIED PRODUCT LISTS.

DETECTABLE WARNING SURFACE SHALL BE PAID FOR AS TRUNCATED DOMES BY THE SQUARE FOOT.

ALL TRUNCATED DOME SYSTEMS SHALL BE PLACED IN STRICT ACCORDANCE WITH THE RECOMMENDATIONS OF THE MANUFACTURER.

- ① CENTER TO CENTER DOME SPACING: 1.6" MINIMUM, 2.4" MAXIMUM.
- ② BASE TO BASE DOME SPACING: 0.65" MINIMUM.
- ③ DOME BASE TO PLATE EDGE SPACING: 0.35" MINIMUM, 0.75" MAXIMUM.
- ④ SPACING VARIES ON RADIAL PLATES.
- ⑤ TYPICAL WIDTHS AVAILABLE: 12", 18", 24", 30", 36". CHECK WITH MANUFACTURERS FOR AVAILABLE WIDTHS.
- ⑥ ON RADIAL PLATE, RADIUS DEFINED AT BACK OF CURB.
- ⑦ TYPICAL RADII. CHECK WITH MANUFACTURERS FOR AVAILABLE RADII.

APPROVED AUGUST 23, 2010

Jon Chad
STATE DESIGN ENGINEER

STATE OF MINNESOTA
DEPARTMENT OF TRANSPORTATION

DETECTABLE WARNING SURFACE
TRUNCATED DOMES

SPECIFICATION
REFERENCE

2531

STANDARD
PLATE
NO.

7038A